State of Vermont

Department of Fish and Wildlife
Department of Forests, Parks and Recreation
Department of Environmental Conservation
State Geologist
Natural Resources Conservation Council

AGENCY OF NATURAL RESOURCES
Department of Environmental Conservation
Barre Regional Office
324 North Main Street
Barre, VT 05641
Telephone 479-3621

September 13, 1993

Fayston School District
German Flats Road
Waitsfield, VT 05673

Dear Chairperson:

RE: WW-5-0415, Fayston School expansion, Fayston

This letter is a follow up to the information submitted for the above-referenced permit.

Based upon the information received from Charles Grenier, conditions 2.2, 2.3 and 3.3 of the above-referenced permit have been satisfied.

If you have any questions, please contact this office.

Sincerely,

Donald Wernecke
Regional Engineer

CC Charles Grenier
Washington West Supervisory Union

State of Vermont

AGENCY OF NATURAL RESOURCES

WATER SUPPLY AND WASTEWATER DISPOSAL PERMIT

CASE No: WW-5-0415 (REVISED)
APPLICANT: Fayston School District
ADDRESS: German Flats Road
Waitsfield, VT 05673

LAWS/REGULATIONS INVOLVED
10 V.S.A. Chapter 61, Water Supply and Wastewater Disposal
Environmental Protection Rules
Chapter 4, Public Buildings
Chapter 7, Sewage Disposal
Chapter 8, Water Supply
Appendix A, Design Guidelines

This project, consisting of expansion of the Fayston Elementary School for a total enrollment of 235 students and staff, located on German Flats Road, Fayston, Vermont, is hereby approved under the requirements of the regulations named above, subject to the following conditions:

1. GENERAL CONDITIONS

1.1. The project must be completed as shown on the plans listed in Water Supply and Wastewater Disposal permit number WW-5-0415, dated 8/26/92, and which have been stamped "APPROVED" by the Division of Protection. No alteration of these plans shall be allowed except where written application has been made to the Agency of Environmental Conservation and approval obtained.

1.2. This revised permit is being issued to reflect the enrollment of the Fayston Elementary School and to correct a condition relating to the water supply.

1.3. All general conditions set forth in Water Supply and Wastewater Disposal Permit number WW-5-0415, dated 8/26/92, shall remain in effect.

2. WATER CONDITIONS

2.1. This project is approved with an on-site water supply from a drilled well provided that the well is located as shown on the plans and no closer than 100 feet to any subsurface wastewater disposal system, 50 feet from any septic tanks, and 50 feet from any sewer lines.

2.2. The water system shall be operated at all times in a manner that keeps the water supply free from contamination. Prior to use of the water supply the water shall be sampled and tested for biological, chemical, and physical content, and must be found to meet the state drinking water standards. Copies of the test results must be submitted to this office.

2.3. The installation of the water supply system shall be inspected by a Vermont registered Professional Engineer who shall report in writing, prior to occupancy, that the work has been completed in accordance with the approved plans.

3. SEWAGE CONDITIONS

3.1. All sewage conditions set forth in Water Supply and Wastewater Disposal Permit number WW-5-0415, dated 8/26/92, shall remain in effect except as amended or modified herein.

Elizabeth A. McLain, Commissioner
Department of Environmental Conservation

By _____ 11/12/92
Don Wernecke, Assistant Regional Engineer

CC Charles Grenier
Washington West Supervisory Union
VT Dept. of Labor & Industry
Town Planning Commission
P. Howard Flanders

State of Vermont

AGENCY OF NATURAL RESOURCES
WATER SUPPLY AND WASTEWATER DISPOSAL PERMIT

CASE No: WW-5-0415
APPLICANT: Fayston School District
ADDRESS: German Flats Road
Waitsfield, VT 05673

LAWS/REGULATIONS INVOLVED
10 V.S.A. Chapter 61, Water Supply and Wastewater Disposal
Environmental Protection Rules
Chapter 4, Public Buildings
Chapter 7, Sewage Disposal
Chapter 8, Water Supply
Appendix A, Design Guidelines

This project, consisting of expansion of the Fayston Elementary School, located on German Flats Road, Fayston, Vermont, is hereby approved under the requirements of the regulations named above, subject to the following conditions:

1. GENERAL CONDITIONS

1.1. The project must be completed as shown on the plans prepared by Charles Grenier and listed as follows:
Site Plan, C1 of C6, Dated 8/6/92,
Site Plan, C2 of C6, Dated 8/6/92,
Pump Station Details, C3 of C6, Dated 8/6/92,
Septic System Details, C4 of C6, Dated 8/6/92,
Water System Details, C5 of C6, Dated 8/6/92,
and which have been stamped "APPROVED" by the Division of Protection. No alteration of these plans shall be allowed except where written application has been made to the Agency of Environmental Conservation and approval obtained.

1.2. A copy of the approved plans and the Water Supply and Wastewater Disposal Permit shall remain on the project during all phases of construction and, upon request, shall be made available for inspection by State or Local personnel.

1.3. No alterations to the existing building other than those indicated on the approved plan, which would change or affect the interior waste plumbing, water supply, or wastewater disposal shall be allowed without prior review and approval from the Agency of Environmental Conservation.

1.4. This authorization does not relieve you, as applicant, from obtaining all approvals and permits as may be required from the Department of Labor and Industry (phone 828-2106) and local officials PRIOR to construction.

1.5. By acceptance of this permit the permittee agrees to allow representatives of the State of Vermont access to the property covered by the permit, at reasonable times, for the purpose of ascertaining compliance with Vermont environmental and health statutes and regulations and with the permit.

1.6. This permit shall in no way relieve you of the obligations of Title 10, Chapter 48, Subchapter 4, for the protection of groundwater.

2. WATER CONDITIONS

2.1. This project is approved with an on-site water supply from an existing drilled well provided that the well is located as shown on the plans and no closer than 100 feet to any subsurface wastewater disposal system, 50 feet from any septic tanks, and 50 feet from any sewer lines.

2.2. The water system shall be operated at all times in a manner that keeps the water supply free from contamination. Prior to use of the water supply the water shall be sampled and tested for biological, chemical, and physical content, and must be found to meet the state drinking water standards. Copies of the test results must be submitted to this office.

2.3. Prior to occupancy of any of the dwelling units within the project, the water distribution system shall be adequately chlorinated, thoroughly flushed and subsequently tested for bacteriological content. The system shall only be put into use after favorable water test results are obtained. A copy of the results must be submitted to this office.

(CONTINUED)